

DAY PUBLIC SCHOOL



KAILASH HILLS, NEW DELHI

CBSE Affiliation No.: 2730186

School ID.: 1925262

Ref. No. DAVPSKHI. 24-25 / 22444 A

15/01/25.

TENDER NOTICE

1	Name of the works	To reconstruct part of the boundary wall of the School.				
2	Time of completion	30-40 days				
3	Date of Tender Notification	13-01-2025				
4	Last Date/Time for Receipt of Bids	20-01-2025				
5	Estimated value of tender	Rs 9,69,233/-				
6	Name and Address of office Inviting Tender	DAV Public School, Near C – block, Kailash Hills, Delhi - 110065				
7	Contact Number	011-46544839, 011-26842283				

GENERAL TERMS & CONDITIONS

- 1. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school shall deduct TDS as per rules of Income Tax Department, Government of India
- 2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept, the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/she may decide.
- 3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Delhi as well as Govt. of India.
- 4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason thereof.

Phone: 011-46544839, 011-26842283 E-mail: info.davkailashhills@gmail.com, davkhills@hotmail.com Website: www.davkailashhills.com



DAY PUBLIC SCHOOL



KAILASH HILLS, NEW DELHI

CBSE Affiliation No.: 2730186

School ID.: 1925262

Ref. No. DAVPSKH/ 24-25/22444 A

15/01/25.

- 5. The rates quoted by the contractor shall hold good upto finishing of the renovation Works. No amendment will be accepted in the rate of renovation.
- 6. The description of the said renovation works in details can be had from the office of the Principal of DAV Public school, Kailash Hills, Delhi. The payment will be made to the contractor through A/c payee cheque as per the running bills submitted after the finishing of the work and duly approved by the architect.
- 7. Quotations which do not comply with the above conditions are liable to be rejected.
- 8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building sub-committee, except the special circumstances if any.
- 9. Defect Liability Period : A security deposit of 10% to be deducted from the final bill upto defect liability period i.e. 12 months.
- 10. The rates are inclusive of all taxes and duties.
- 11. Work should be carried as per CPWD specifications.
- 12. No damage is caused to school property while execution of work otherwise the contractor will be liable to make for loss/damage.
- 13. The contractor should follow all compliances of local authorities i.e. MCD/DDA etc.

PRINCIPAL

BOQ FOR DEMOLITION & RE - CONSTRUCTION OF PART BOUNDARY WALL AT DAV PUBLIC SCHOOL KAILASH HILLS, DELHI

.No	DSR No.	DESCRIPTION OF ITEMO	QUANTITY	UNIT	RATE	AMOUNT
1	15.60 u	Disposal of building rubbish / malba / similar unserviceable, dismantled or vaste materials by mechanical means, including loading, transporting, inloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	45.00	Cum		
2	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	281	All kinds of soil.	50.00	Cum		
3	2.90	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.				
	2.9.1	Ordinary Rock	50	Cum		
4	The Control of the Co	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	70.00	Cum		
5	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
	6.4.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	34.50	Cum		
6	13.1	12 mm cement plaster of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	415.00	Sqm		
7	13.8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	415	Sqm		
8	13.47	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:				
	13.47.1	New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	415.00	Sqm		
9	16.18	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used.	f			
	16.18.1	With G.I. barbed wire	175	metre		
10	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	1109	Kg		
	13.14	15mm cement plaster 1:2 (1 cement : 2 stone dust) on the rough side of brid wall.		Sqm.		
	10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.	ng			
	10.25.1	Iniate wherever required, all complete.		Kg		
	10.25.	IWORKS.		Kg		
	5.4	Providing and laying reinforced cement concrete in kerbs, steps and the like or near ground level excluding the cost of centering, shuttering, finishing at reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	nd 5.00	Cum		

	All the rates are as per DSR 2023 & DSR 2022 (Electrical) wherever DSR code number is mentioned. The school may negotiate on the abovementioned rates from the contractors as this is a cost estimate.				
Notes:	All the rates are inclusive of GST		Grand Total	0.00	
	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	175.00	Sqm.		