

TENDER NOTICE

Ref No.:

Dated: 25/12/2025

1	Name of the works	Construction of MS Staircase from Ground Floor to Second Floor
2	Time of completion	30 Days
3	Date of Tender Notification	26.12.2025
4	Last Date/Time for Receipt of Bids	09.01.2026
5	Cost of Tender Document	Rs 1500/-
6	Estimated value of tender	Rs 11,35,000/-
7	Name and Address of office Inviting Tender	DAV Public School, Near C – block, Kailash Hills, Delhi - 110065
8	Contact Number	011-26842283

GENERAL TERMS & CONDITIONS

1. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school shall deduct TDS as per rules of Income Tax Department, Government of India
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept, the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/she may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Delhi as well as Govt. of India.

4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason thereof.
5. The rates quoted by the contractor shall hold good upto finishing of the renovation Works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of from the Principal of DAV Public school, Kailash Hills, Delhi. The payment will be made to the contractor through A/c payee cheque as per the running bills submitted after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building sub-committee, except the special circumstances if any.
9. Defect Liability Period : A security deposit of 10% to be deducted from the final bill upto defect liability period i.e. 12 months.
10. The rates are inclusive of all taxes and duties.
11. Work should be carried as per CPWD specifications.
12. No damage is caused to school property while execution of work otherwise the contractor will be liable to make for loss/damage.
13. The contractor should follow all compliances of local authorities i.e. MCD/DDA etc.

PRINCIPAL

**BOQ FOR MS STAIRCASE FROM GROUND FLOOR TO SECOND FLOOR FROM CANTEEN SIDE
AT DAV PUBLIC SCHOOL, KAILASH HILLS, DELHI**

Date : 25.12.2025

Sl. No	DSR Code No.	Description of Item	Qty.	Unit	Rate (INR)	Amount (INR)
1	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	3600	kg		0
2	10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	10.25.1	In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete.	1020	kg		0
3	10.26	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.				
	10.26.1	M.S. tube.	700	kg		0
4	13.50	Applying priming coat :	200			
	13.50.3	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/steel works	100	Sqm		0
5	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				
	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	200	Sqm		0
6	10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
	10.16.1	Hot finished welded type tubes.	900	kg		0

7	4.1.3	Grouting base plates with cement concrete	4	Nos		0
8	NS	Miscellaneous (fasteners, foundation blocks of RCC, scaffolding)	1	LS		0
9	NS	Dismantling of existing stairacase, including disposing of the malba, clearing the site to install the MS staircase.	1	LS		0
10	NS	Civil work for connecting it to the building block from canteen side, MS railing etc.	1	LS		0
					Grand Total	0.00

Notes :	All the rates are inclusive of GST
	All the rates are as per DSR 2023 & DSR 2022 (Electrical) wherever DSR code number is mentioned. The school may negotiate on the above-mentioned rates from the contractors as this is a cost estimate.
	Few items have been foreseen in shifting of services and few extra items will need to incorporated as per site conditions.