

TENDER NOTICE

Ref No.:

Dated: 17/08/2026

1	Name of the works	Dismantling old damaged roofing and P/F new roofing at Junior Wing DAV Public School
2	Time of completion	45 Days
3	Date of Tender Notification	23.08.2026
4	Last Date/Time for Receipt of Bids	31.08.2026
5	Cost of Tender Document	Rs 2500/-
6	Estimated value of tender	Rs 7,90,000/-
7	Name and Address of office Inviting Tender	DAV Public School, Near C – block, Kailash Hills, Delhi - 110065
8	Contact Number	011-26842283
9	EMD Deposit	Rs 30,000/-

GENERAL TERMS & CONDITIONS

1. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school shall deduct TDS as per rules of Income Tax Department, Government of India
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept, the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/she may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Delhi as well as Govt. of India.

4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason thereof.
5. The rates quoted by the contractor shall hold good upto finishing of the renovation Works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of from the Principal of DAV Public school, Kailash Hills, Delhi. The payment will be made to the contractor through A/c payee cheque as per the running bills submitted after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building sub-committee, except the special circumstances if any.
9. Defect Liability Period : A security deposit of 10% to be deducted from the final bill upto defect liability period i.e. 12 months.
10. The rates are inclusive of all taxes and duties.
11. Work should be carried as per CPWD specifications.
12. No damage is caused to school property while execution of work otherwise the contractor will be liable to make for loss/damage.
13. The contractor should follow all compliances of local authorities i.e. MCD/DDA etc.
14. The Contractor shall verify all quantities, dimensions, and BOQ items before commencement of work after award of tender, and any discrepancy or extra item identified shall be intimated in writing to the Architect and School Management prior to execution of the affected work, failing which no extra item or additional quantity shall be considered valid or payable, and written approval from the School Management is mandatory before proceeding with any extra or additional work.

PRINCIPAL

BOQ for Dismantling old damaged roofing and P/F new roofing at DAV Public School (Junior Wing), Kailash Hills , Delhi.

S.NO.	DSR No.	Description of items	Qty.	Unit	Rate	Amount
1	12.5	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	425	sqm		
2	12.51	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :				
a	12.51.6	Gutter (600 mm over all girth)	85	mtr		
b	12.51.2	Flashings/ Aprons.(Upto 600 mm)	101	mtr		
3	15.28.1	Dismantling roofing /cutting the damaged portion of sheet along the width including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	425	sqm		
4	21.8.1	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete. Upto 5mm depth and 5 mm width	18	mtr		
5	10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	10.25.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	825	kg		
6	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A,				

		including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
	12.41.2	110 mm diameter	57	mtr		
7	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion				
a	12.42.1.1	Coupler 110mm	15	each		
b	12.42.5.2	Bend 87.5° 110mm	19	each		
8	12.38	Providing and fixing M.S. holder bat clamps of approved design to C.I. or S.C.I. rain water pipes embedded in and including cement concrete blocks 10x10x10 cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and cost of cutting holes and making good the walls etc. :				
	12.38.1	100 mm diameter	38	each		
9	13.53.1	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : New work (two or more coats) steel primer but excluding a coat of mordant solution	430	sqm		
10	13.54.1	Applying a coat of mordant solution on G.S. sheet: With a solution of 38 gms of copper acetate in a litre of soft water	430	sqm		
11	NS	Salvage for old GI precoated sheet (425sqm)	1160	kg		
					Total	0.00
Notes :	All the rates are inclusive of GST					
	All the rates are as per DSR 2023 & DSR 2022 (Electrical) wherever DSR code number is mentioned. The school may negotiate on the above-mentioned rates from the contractors as this is a cost estimate.					
	Few items have been foreseen in shifting of services and few extra items will need to incorporated as per site conditions.					