



DAV PUBLIC SCHOOL

KAILASH HILLS, NEW DELHI



CBSE Affiliation No.: 2730186

School ID.: 1925262

Ref. No. DAVPSKH/24-25/22477

03/02/25

TENDER NOTICE

1	Name of the works	To construct the Parapet wall on the second floor of Block C of the school building.
2	Time of completion	30-40 days
3	Date of Tender Notification	03-02-2025
4	Last Date/Time for Receipt of Bids	07-02-2025
5	Estimated value of tender	Rs 17,73,000/-
6	Name and Address of office Inviting Tender	DAV Public School, Near C – block, Kailash Hills, Delhi - 110065
7	Contact Number	011-46544839, 011-26842283

GENERAL TERMS & CONDITIONS

1. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school shall deduct TDS as per rules of Income Tax Department, Government of India
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept, the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/she may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Delhi as well as Govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason thereof.

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

Address : DAV Public School, Kailash Hills, near 'C' Block Market, East of Kailash, New Delhi-110065

Phone : 011-46544839, 011-26842283 E-mail : info.davkailashhills@gmail.com, davkhills@hotmail.com Website : www.davkailashhills.com



DAY PUBLIC SCHOOL

KAILASH HILLS, NEW DELHI



CBSE Affiliation No.: 2730186

School ID.: 1925262

Ref. No. DAVPSKH/.....24-25/22477

03/02/25.

5. The rates quoted by the contractor shall hold good upto finishing of the renovation Works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of the Principal of DAV Public school, Kailash Hills, Delhi. The payment will be made to the contractor through A/c payee cheque as per the running bills submitted after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building sub-committee, except the special circumstances if any.
9. Defect Liability Period : A security deposit of 10% to be deducted from the final bill upto defect liability period i.e. 12 months.
10. The rates are inclusive of all taxes and duties.
11. Work should be carried as per CPWD specifications.
12. No damage is caused to school property while execution of work otherwise the contractor will be liable to make for loss/damage.
13. The contractor should follow all compliances of local authorities i.e. MCD/DDA etc.


PRINCIPAL

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

Address : DAV Public School, Kailash Hills, near 'C' Block Market, East of Kailash, New Delhi-110065

Phone : 011-46544839, 011-26842283 E-mail : info.davkailashhills@gmail.com, davkhills@hotmail.com Website : www.davkailashhills.com

BOQ FOR PARAPET WALL IN BLOCK - C, DAV PUBLIC SCHOOL, KAILASH HILLS

S. No.	DSR Code No.	Description of Items	Qty.	Unit	Rate	Amount
1	6.4	Brick work with common burnt clay F.P.S. (non - modular) bricks of designation 7.5 in superstructure above plinth level upto floor V level in all shapes & sizes in :				
	6.4.1	Cement mortar 1:6 (1 cement : 4 coarse sand)	50	Cum		
2	13.14	15mm cement plaster 1:2 (1 cement : 2 stone dust) on the rough side of single or half brick wall.	432.00	Sqm.		
3	13.1	12 mm cement plaster of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	432.00	Sqm.		
4	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, all loads including all lifts involved. Note:- Malba quantity is equal to dismantled material / items.	8.00	Cum		
5	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. Make :- JK., Birla	864.00	Sqm.		

6	13.47	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade				
7	13.47.1	New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm) Make : Asian, Berger, Birla opus)	864.00	Sqm.		
8	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	60.00	Sqm.		
9	14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for	1440.00	Sqm.		
10	6.4	Extra for providing & placing in position 2 nos. 6mm dia MS Bars at every third course of half brick masonry.	132.48	Sqm.		
11	5.2	RCC in columns*	7.00	Cum		
12	5.3	RCC in beams*	24.00	Cum		
13	5.9	Formwork*				
14	5.9.5	Beams*	282.42	Sqm		
15	5.9.6	Columns*	85.00	Sqm		
16	5.22A.6	Steel Reinforcement*	2000.00	kg		
						Total
Note : All the rates are inclusive of GST						
*Subject to approval from the Structural Engineer.						