



DAV PUBLIC SCHOOL

KAILASH HILLS, NEW DELHI



DAVPS KH/24-25/22167

TENDER NOTICE

13/06/24

Ref. No. DAVPSKH/24-25/22167

1	Name of the works	Renovation work in senior building false ceiling, flooring in 8 classrooms
2	Time of completion	70 Days
3	Date of Tender Notification	13.06.2024
4	Last Date/Time for Receipt of Bids	18.06.2024
5	Cost of Tender Document	Rs 2500/- (draft in favour of DAV Public School, Kailash Hills, Delhi)
6	Estimated value of tender	Rs 15,91,308/-
7	Name and Address of office Inviting Tender	DAV Public School, Near C – block, Kailash Hills, Delhi - 110065
8	Contact Number	011-46544839, 011-26842283

GENERAL TERMS & CONDITIONS

1. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school shall deduct TDS as per rules of Income Tax Department, Government of India
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept, the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/she may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Delhi as well as Govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason thereof.

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

Address: DAV Public School, Kailash Hills, near 'C' Block Market, East of Kailash, New Delhi-110065

Phone : 011-26842283 Fax : 011-26919041 E-mail : davkhills@hotmail.com Website : www.davkailashhills.com



DAY PUBLIC SCHOOL

KAILASH HILLS, NEW DELHI



13/06/24

5. The rates quoted by the contractor shall hold good upto finishing of the renovation Works. No amendment will be accepted in the rate of renovation.
Ref. No. DAVPSKH/DAV.K.H.124-25/22-167

6. The description of the said renovation works in detail can be had from the office of the Principal of DAV Public school, Kailash Hills, Delhi. The payment will be made to the contractor through A/c payee cheque as per the running bills submitted after the finishing of the work and duly approved by the architect.

7. Quotations which do not comply with the above conditions are liable to be rejected.

8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building sub-committee, except the special circumstances if any.


9. Defect Liability Period : A security deposit of 10% to be deducted from the final bill upto defect liability period i.e. 12 months.

10. The rates are inclusive of all taxes and duties.

11. Work should be carried as per CPWD specifications.

12. No damage is caused to school property while execution of work otherwise the contractor will be liable to make for loss/damage.

13. The contractor should follow all compliances of local authorities i.e. MCD/DDA etc.


Gargi Chhabra
Principal

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

Address: DAV Public School, Kailash Hills, near 'C' Block Market, East of Kailash, New Delhi-110065

Phone : 011-26842283 Fax : 011-26919041 E-mail : davkhills@hotmail.com Website : www.davkailashhills.com

Bill of Quantities for Miscll. Works (False ceiling & Flooring - 8 rooms) at DAV Public School, Kailash Hills, New Delhi

S. No.	DSR Code No.	Description of Items	Qty.	Unit	Rate	Amount
1	11.26	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand):				
	11.26.1	25 mm thick	360	Sqm		-
2	11.27	Kota stone slabs 20mm thick in risers of steps, skirting, dado & pillars laid on 12mm (average) thick cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of slabs, including rubbing and polishing.	35	Sqm		-
2	13.1	12 mm cement plaster of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	50	Sqm		-
4	13.83	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
	13.83.1	One coat	1250	Sqm		-
	13.83.2	Two coats (Rate only)	1	Sqm		-
5	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	20	Sqm		-
6	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	150	Sqm		-
7	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, all loads including all lifts involved. Note:- Malba quantity is equal to dismantled material / items.	24.00	Cum		-

Gargi

8	26.22	<p>Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanised iron section of 0.33 mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600 mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6 mm thick with precut hole on both 25 mm flange to pierce into 12x50 mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge.</p>			
9	26.22.2	<p>With 15 mm thick tegular/butt edged without perforation plain/designer light weight calcium silicate Anti-Microbial Bio-Safe coated false ceiling tiles Confirming to JIS-Z2801 and ASTM G-21</p>	360.00	Sqm	
	15.13	<p>Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :</p>	8.00	each	
		<p>Of area 3 sq. metres and below</p>			
					<p>Total -</p>

Note : All the rates are inclusive of GST

