



# DAV PUBLIC SCHOOL

KAILASH HILLS, NEW DELHI



CBSE Affiliation No.: 2730186

School ID.: 1925262

Ref. No. DAVPSKH/24-25/22543

03/03/25.

## TENDER NOTICE

1	Name of the works	Waterproofing of terrace in admin block .
2	Time of completion	30 days
3	Date of Tender Notification	3-03-2025
4	Last Date/Time for Receipt of Bids	10-03-2025
5	Estimated value of tender	Rs 16,84,754/-
6	Cost of Tender Document	Rs 2500/-
7	Name and Address of office Inviting Tender	DAV Public School, Near C – block, Kailash Hills, Delhi - 110065
8	Contact Number	011-46544839, 011-26842283

### GENERAL TERMS & CONDITIONS

1. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school shall deduct TDS as per rules of Income Tax Department, Government of India
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept, the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he/she may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Delhi as well as Govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason thereof.

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

Address : DAV Public School, Kailash Hills, near 'C' Block Market, East of Kailash, New Delhi-110065

Phone : 011-46544839, 011-26842283 E-mail : info.davkailashhills@gmail.com, davkhills@hotmail.com Website : www.davkailashhills.com



# DAV PUBLIC SCHOOL

## KAILASH HILLS, NEW DELHI



CBSE Affiliation No.: 2730186

School ID.: 1925262

Ref. No. DAVPSKH/24-25/22543

03/03/25.

5. The rates quoted by the contractor shall hold good upto finishing of the renovation Works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of the Principal of DAV Public school, Kailash Hills, Delhi. The payment will be made to the contractor through A/c payee cheque as per the running bills submitted after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building sub-committee, except the special circumstances if any.
9. Defect Liability Period : A security deposit of 10% to be deducted from the final bill upto defect liability period i.e. 12 months.
10. The rates are inclusive of all taxes and duties.
11. Work should be carried as per CPWD specifications.
12. No damage is caused to school property while execution of work otherwise the contractor will be liable to make for loss/damage.
13. The contractor should follow all compliances of local authorities i.e. MCD/DDA etc.

  
PRINCIPAL

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

Address : DAV Public School, Kailash Hills, near 'C' Block Market, East of Kailash, New Delhi-110065

Phone : 011-46544839, 011-26842283 E-mail : info.davkailashhills@gmail.com, davkhills@hotmail.com Website : www.davkailashhills.com

# BOQ for Waterproofing Work Admin Block Terrace at D.A.V. Public School Kailash

Date: 22-09-2024

S. No.	DSR Code No.	Description of Items	Qty.	Unit	Rate	Amount
1	14.13	Regrading terracing of mud phaska covered with tiles or brick, in cement mortar by dismantling tiles or bricks, removing mud plaster, preparing the surface of mud phaska to proper slope, relaying mud plaster gobri and tiles or bricks, grouted in cement mortar 1:3 (1 cement : 3 fine sand), including replacing unserviceable tiles or bricks with new ones and disposal of unserviceable material to the dumping ground (the cost of the new tiles or brick excluded), all complete as per direction of Engineer-in Charge.	612	sqm		0
2	15.26	Demolishing brick tile covering in terracing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	612	sqm		0
3	15.27	Demolishing mud phaska in terracing and disposal of material within 50 metres lead.	61.2	cum		0
4	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	150	sqm		0
5	15.58	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1 kilometre, stacking serviceable and unserviceable material separately including cutting reinforcement bars	80	cum		0
6	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, all loads including all lifts involved. Note:- Malba quantity is equal to dismantled material / items.	100.00	Cum		0
7	12.22	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1mx1mx400micron, finished with 12mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete.	14.00	Each		0
8	12.44	Providing and fixing to the inlet mouth of rain water pipe cast iron grating 15 cm diameter and weighing not less than 440 grams.	14.00	Each		0
9	13.14	15mm cement plaster 1:2 (1 cement : 2 stone dust) on the rough side of single or half brick wall.	198.00	Sqm.		0
10	12.21	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10mm and down gauge) including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design :				0
10.1	12.21.1	In 75x75mm deep chase	182.00	Meter		0
11	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. Make :- JK., Birla	198.00	Sqm		0
	13.47	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade	0.00			0

12	13.47.1	New work (Two or more coats applied @ 1.43 ltr/ 10 sqm. over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm). Make : Asian, Berger, Nerolac.	198.00	Sqm		0
13	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				0
13.1	12.41.1	75 mm diameter	10	Meter		0
13.2	12.41.2	110 mm diameter	21	Meter		0
14	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				0
14.1	6.4.1	Cement Mortar 1:4 (1 cement : 4 coarse sand)	14.49	cum		0.00
15	5.2	RCC in columns*	7.00	Cum		0
16	5.9	Formwork*				0
17	5.9.6	Columns*	4.05	Sqm		0
18	7904	Burnt clay tile bricks.	15000	Nos		0
19	14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chaises, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	1000.00	Sqm		0
20	114	Beldar	15.00	Nos.		0
21	123	Mason 1st class	15.00	Nos.		0
					Total	0.00
<b>Notes : All the rates are inclusive of GST</b>						
All the rates are as per DSR 2023 & DSR 2022 (Electrical) wherever DSR code number is mentioned. The school may negotiate on the above-mentioned rates from the contractors as this is a cost estimate.						